## Addendum No. 2 August 16, 2023

### Theron W. Ward Judicial Building Remodel and Expansion

This addendum addresses the following:

- Bid package revisions
- Addendum 2 from CSHQA
- Preliminary Master Schedule

### Attachments

- Revised bid packages
- CSHQA Addendum 2 dated August 11, 2023
- Preliminary master schedule

End of Add. No. 2



# Theron W Ward Judicial Building Remodel and Expansion Bids to Starr Corporation by August 24, 2023, at 2:00 PM

Bid Package No.	Package Description	Spec Section	Description	Additional Comments - (All items include material, labor, and equipment for installation)
1	Site	Division 1	General Requirements	All sections to be included in their entirety.
1	Site	310000	Earthwork	Add No. 2–All work to comply with ISPWC. Scope includes the following-Clear and Grub Site, Construction Building Pad, Excavate and Backfill for Foundation, Install Gravel for site concrete, provide gravel for SOG, Install Site Utilities to 5' outside of building, Install Storm drainage system, prepare landscape areas to +/-0.1', patch asphalt, and install fire line to 1'AFF. Clear and grub parking area, install gravel base, asphalt paving, and striping for parking area. Rock removal is anticipated. The owner will provide trucking, on site, as needed to facilitiate off haul of excavation spoils and duff.
2	Demolition	Division 1	General Requirements	All sections to be included in their entirety.
2	Demolition	024100	Demolition	
3	Landscaping Landscaping	Division 1 328423	General Requirements Underground Sprinklers	All sections to be included in their entirety.
3	Landscaping	329223	Sodding	
3	Landscaping	329300	Plants	
4	Cast in Place Concrete	Division 1	General Requirements	All sections to be included in their entirety.
4	Cast-in-place Concrete Cast-in-place Concrete	030516 032000	Underslab Vapor Barrier Concrete Reinforcing	
			Cast-in-Place Concrete	Install anchor bolts and grout bed for anchor bolts provided by others. Install gravel for building SOG, gravel provided by
4	Cast-in-place Concrete Cast-in-place Concrete	033000 072100	Thermal Insulation	others. Insulation for concrete foundation only.
4 4	Cast-in-place Concrete	071113 071300	Bituminous Dampproofing	
4	Cast-in-place Concrete Cast in Place Concrete	071300	Sheet Waterproofing Joint Sealants	Sealants for Concrete Scope Only
4	Cast in Place Concrete	323300	Site Furnishings	
5	Masonry	Division 1	General Requirements	All sections to be included in their entirety.
5	Masonry	042000	Unit Masonry	
5	Masonry	042200	Concrete Unit Masonry	Reinforcing included in this scope of work. Bucks, as needed for this scope are included in this package.
5	Masonry	047200	Cast Stone Masonry	
5	Masonry	072500	Weather Barriers	Addendum No 2 - Provide and install barrier on wall surface behind mason veneer and GFRC.
5	Masonry	079200	Joint Sealants	Sealants for masonry joints included in this scope of work.
6	Structural Steel-Supply and Install	Т	Complete work listed in Bid Package 6A and 6B	
6A	Structural Steel (Supply)	Division 1	General Requirements	All sections to be included in their entirety.  Supply only, install by others. Provide anchor bolts to be
6A	Structural Steel (Supply)	051200	Structural Steel Framing	installed by others.
6A 6A	Structural Steel (Supply) Structural Steel (Supply)	052100 053100	Steel Joist Framing Steel Decking	Supply only, install by others. Supply only, install by others.
6A	Structural Steel (Supply)	055000	Metal Fabrications	Supply only, install by others.
6A 6A	Structural Steel (Supply) Structural Steel (Supply)	055113 055133	Metal Pan Stairs  Metal Ladders	Supply only, install by others. Supply only, install by others.
6A	Structural Steel (Supply)	055213	Pipe and Tube Railings	Supply only, install by others.
6A 6A	Structural Steel (Supply) Structural Steel (Supply)	057000 057100	Decorative Metal Decorative Metal Stairs	Supply only, install by others. Supply only, install by others.
CD.		Division 4	Consert Provinces sets	
6B 6B	Structural Steel (Install) Structural Steel (Install)	Division 1 051200	General Requirements Structural Steel Framing	All sections to be included in their entirety.  Install only, supplied by others
6B	Structural Steel (Install)	052100	Steel Joist Framing Steel Decking	Install only, supplied by others
6B 6B	Structural Steel (Install) Structural Steel (Install)	053100 055000	Metal Fabrications	Install only, supplied by others Install only, supplied by others
6B 6B	Structural Steel (Install) Structural Steel (Install)	055113 055133	Metal Pan Stairs  Metal Ladders	Install only, supplied by others Install only, supplied by others
6B	Structural Steel (Install)	055213	Pipe and Tube Railings	Install only, supplied by others
6B 6B	Structural Steel (Install) Structural Steel (Install)	057000 057100	Decorative Metal Decorative Metal Stairs	Install only, supplied by others Install only, supplied by others
	,			7. 11
7	Millwork Millwork	Division 1 064100	General Requirements  Architectural Wood Casework	All sections to be included in their entirety.  Please note AWI requirements-Provide and install backing as needed for this scope of work.
7	Millwork	064113	Wood Veneer Faced Architectural Cabinets	Provide and install backing as needed for this scope of work.
7	Millwork	064216	Flush Wood Paneling	Provide and install backing as needed for this scope of work.
7	Millwork	064400	Ornamental Woodwork	Provide and install backing as needed for this scope of work.
7	Millwork	066100	Cast Polymer Fabrications	Provide and install backing as needed for this scope of work.
7	Millwork	123600	Countertops	Provide and install backing as needed for this scope of work.
8	Rough Carpentry	Division 1 061053	General Requirements	All sections to be included in their entirety.
8	Rough Carpentry Rough Carpentry	113013	Miscellaneous Rough Carpentry Residential Appliances	
8	Rough Carpentry	323113	Chainlink Fences and Gates	
9	Roofing	Division 1	General Requirements	All sections to be included in their entirety.
9	Roofing	070750.19	Preparation for Re-Roofing Thermal Insulation	
9	Roofing Roofing	072100 075400	Thermal insulation Thermoplastic Membrane Roofing	As included in the roof system only.
9	Roofing Roofing	076200 077100	Sheet Metal Flashing and Trim Roof Specialties	As needed for roofing system
9	Roofing	077200	Roof Accessories	
9	Roofing	079200	Theron 9in Waral Bits Packages	Sealants for this scope of work only.

1				
10	Insulation	Division 1	General Requirements	All sections to be included in their entirety.
10	Insulation	072100	Thermal Insulation	Insulation in the roofing system and foundation insulation are specifically excluded.
10	Insulation	072119	Foamed-In-Place Insulation	
10	Insulation	079200	Joint Sealants	Sealants for this scope of work only.
11	Doors and Hardware	Division 1	General Requirements	All sections to be included in their entirety.
				Includes metal hollow frames, doors, door louvers, transom, sidelite and borrow lite frames and hardware. Note: This
				section to include all hollow metal window frames per the
11	Doors and Hardware	081113	Hollow Metal Doors and Frames	drawings and specifications. Glazing by others.
11 11	Doors and Hardware Doors and Hardware	081416 083100	Flush Wood Doors Access Doors and Panels	
	Bools and Hardware	000100	700000 Boots and Fancis	Provide hardware for doors and jambs supplied under this
44	Deers and Hardware	007100	Door Hardware	package only. Air lines for air actuated locks installed by
11 11	Doors and Hardware  Doors and Hardware	087100 111400	Pedestrian Control Equipment	others.
11	Doors and Hardware	111913	Detention Hollow Metal Doors and Frames	
11	Doors and Hardware	111953	Detention Hardware	
12	Glazing	Division 1	General Requirements	All sections to be included in their entirety.
12	Glazing	084313	Aluminum Framed Storefronts Glazed Aluminum Curtain Walls	
12	Glazing	084413	Giazed Aluminum Curtain Walls	Provide hardware for doors and jambs supplied under this
12	Glazing	087100	Door Hardware	package only.
12 12	Glazing Glazing	088000 088813	Glazing Fire Rated Glazing	
12	Glazing	111908	Security Glazing	
12	Glazing	076200	Sheet Metal Flashing and Trim	Flashing as applies to storefront and curtain wall system.
12	Glazing	079200	Joint Sealants	Only as they apply to the work of this package; includes all sealants that touch glazing
		•		
13	Gypsum Board Systems	Division 1	General Requirements Cold Formed Metal Framing	All sections to be included in their entirety.
13 13	Gypsum Board Systems Gypsum Board Systems	054000 068316	Fiberglass Reinforced Paneling	
13	Gypsum Board Systems	070553	Fire and Smoke Assembly Identification	
				Only as applied to this scope of work. All penetrations by other trades will be firestopped by the trade that makes the
13	Gypsum Board Systems	078400	Firestopping	penetration.
13	Gypsum Board Systems	079513	Expansion Joint Cover Assemblies	
13 13	Gypsum Board Systems Gypsum Board Systems	079210 092116	Security Joint Sealants Gypsum Board Assemblies	
13	Gypsum Board Systems	092216	Non-Structural Metal Framing	
13 13	Gypsum Board Systems	095100 098430	Acoustical Ceilings Sound Absorbing Wall and Ceiling Units	
13	Gypsum Board Systems	090430	Sound Absorbing Wall and Celling Units	
<del>13</del>	Gypsum Board Systems	<del>111950</del>	Detention Ceiling Panel Systems	Addendum 2 - removed from bid package 13 and added to 19
<del>13</del>	Gypsum Board Systems	<del>111951</del>	Detention Ceiling Panel Systems	Addendum 2 - removed from bid package 13 and added to 19
13	Gypsum Board Systems	102641	Bullet Resistant Panels	
13	Gypsum Board Systems	134813	Manufactured Sound and Vibration Control Components	
15	Cypsum Board Cystems	134013	Manufactured Count and Vibration Control Components	
14	GFRC-Supply and Install	Division 1	General Requirements	All sections to be included in their entirety.
14	GFRC-Supply and Install	_	Complete work listed in Bid Package 14A and 14B	
14A	GFRC-Supply Only	Division 1	General Requirements	All sections to be included in their entirety.
14A	GFRC-Supply Only	034900	Glass Fiber Reinforced Concrete	Supply and deliver to site
14B	GFRC-Install Only	Division 1	General Requirements	All sections to be included in their entirety.
			0 5 5 6 10	Installation only. Materials provided by others. Includes
14B	GFRC-Install Only	034900	Glass Fiber Reinforced Concrete	receiving material on site, unloading, and staging on site.
15	Flooring	Division 1	General Requirements	All sections to be included in their entirety.
15			Complete work listed in Bid Package 15A and 15B	
154				
15A	Tile	Division 1	General Requirements	All sections to be included in their entirety.
			·	·
15A 15A	Tile Tile	Division 1 093000	General Requirements Tiling	All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.
			·	·
15A 15B	Tile Flooring	093000 Division 1	Tiling  General Requirements	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.
15A	Tile	093000	Tiling	Joint and crack filling, minor leveling, and sanding is included.
15A 15B	Tile Flooring	093000 Division 1	Tiling  General Requirements	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.
15A 15B 15B 15B	Tile Flooring Flooring Flooring	093000  Division 1  096500  096813	Tiling  General Requirements  Resilient Flooring  Tile Carpeting	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.
15A 15B 15B 15B 16 16	Tile Flooring Flooring Flooring Painting Painting	093000  Division 1  096500  096813  Division 1  099113	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.
15A 15B 15B 15B 15B	Tile  Flooring  Flooring  Flooring  Painting  Painting  Painting  Painting	093000  Division 1  096500  096813  Division 1  099113  099123	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting  Interior Painting	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.
15A 15B 15B 15B 16 16	Tile Flooring Flooring Flooring Painting Painting	093000  Division 1  096500  096813  Division 1  099113	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.
15A 15B 15B 15B 15B 16 16 16 16	Tile Flooring Flooring Flooring Painting Painting Painting Painting Painting	093000  Division 1  096500  096813  Division 1  099113  099123  099600	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting  Interior Painting  High Performance Coatings	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Pre-Prime all surfaces prior to application of spray texture.
15A 15B 15B 15B 15B 16 16 16 16 16 16 16	Tile  Flooring  Flooring  Flooring  Painting  Painting  Painting  Painting  Painting  Painting  Painting  Painting  Painting	093000  Division 1 096500 096813  Division 1 099113 099123 099600 033511 071900	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting  Interior Painting  High Performance Coatings  Concrete Floor Finishes  Water Repellents	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Pre-Prime all surfaces prior to application of spray texture.  All interior sealants exclusive of glazing, concrete, and
15A  15B  15B  15B  16  16  16  16  16  16  16  16  16	Tile  Flooring  Flooring  Painting	093000  Division 1 096500 096813  Division 1 099113 099123 099600 033511 071900 079200	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting  Interior Painting  High Performance Coatings  Concrete Floor Finishes  Water Repellents  Joint Sealants	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Pre-Prime all surfaces prior to application of spray texture.  All interior sealants exclusive of glazing, concrete, and millwork.
15A  15B  15B  15B  16  16  16  16  16  16  16  17	Tile  Flooring  Flooring  Flooring  Painting	093000  Division 1 096500 096813  Division 1 099113 099123 099600 033511 071900 079200  Division 1	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting Interior Painting High Performance Coatings Concrete Floor Finishes Water Repellents  Joint Sealants  General Requirements	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Pre-Prime all surfaces prior to application of spray texture.  All interior sealants exclusive of glazing, concrete, and
15A  15B  15B  15B  16  16  16  16  16  16  16  16  16	Tile  Flooring  Flooring  Painting	093000  Division 1 096500 096813  Division 1 099113 099123 099600 033511 071900 079200	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting  Interior Painting  High Performance Coatings  Concrete Floor Finishes  Water Repellents  Joint Sealants	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Pre-Prime all surfaces prior to application of spray texture.  All interior sealants exclusive of glazing, concrete, and millwork.
15A  15B  15B  15B  16  16  16  16  16  16  17  17	Tile  Flooring  Flooring  Flooring  Painting	093000  Division 1 096500 096813  Division 1 099113 099123 099600 033511 071900  Division 1 072423  Division 1	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting Interior Painting High Performance Coatings Concrete Floor Finishes Water Repellents  Joint Sealants  General Requirements Direct Applied Finish System  General Requirements	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Pre-Prime all surfaces prior to application of spray texture.  All interior sealants exclusive of glazing, concrete, and millwork.  All sections to be included in their entirety.
15A  15B  15B  15B  16  16  16  16  16  16  17  17  18  18	Tile  Flooring  Flooring  Flooring  Painting  Painting  Painting  Painting  Painting  Painting  Painting  Painting  Painting  Pointing  Pointing  Pointing  Pointing  Pointing  Pointing  Pointing  Pointing  DEFS  DEFS  Specialties  Specialties	093000  Division 1  096500  096813  Division 1  099113  099600  033511  071900  Division 1  072423  Division 1  061000	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting Interior Painting High Performance Coatings Concrete Floor Finishes Water Repellents  Joint Sealants  General Requirements Direct Applied Finish System  General Requirements Rough Carpentry	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Pre-Prime all surfaces prior to application of spray texture.  All interior sealants exclusive of glazing, concrete, and millwork.  All sections to be included in their entirety.  All sections to be included in their entirety.  Install backing necessary to complete this scope of work.
15A  15B  15B  15B  16  16  16  16  16  16  17  17	Tile  Flooring  Flooring  Flooring  Painting	093000  Division 1 096500 096813  Division 1 099113 099123 099600 033511 071900  Division 1 072423  Division 1	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting Interior Painting High Performance Coatings Concrete Floor Finishes Water Repellents  Joint Sealants  General Requirements Direct Applied Finish System  General Requirements	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Pre-Prime all surfaces prior to application of spray texture.  All interior sealants exclusive of glazing, concrete, and millwork.  All sections to be included in their entirety.
15A  15B  15B  15B  16  16  16  16  16  17  17  18  18  18  18  18	Tile  Flooring  Flooring  Flooring  Painting  Painting  Painting  Painting  Painting  Painting  Painting  DEFS DEFS  Specialties Specialties Specialties Specialties Specialties Specialties Specialties	093000  Division 1  096500  096813  Division 1  099113  099123  099600  033511  071900  Division 1  072423  Division 1  061000  079200  101400  101416	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting Interior Painting High Performance Coatings Concrete Floor Finishes Water Repellents  Joint Sealants  General Requirements Direct Applied Finish System  General Requirements Rough Carpentry Joint Sealants  Signage Plaques	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Pre-Prime all surfaces prior to application of spray texture.  All interior sealants exclusive of glazing, concrete, and millwork.  All sections to be included in their entirety.  All sections to be included in their entirety.  Install backing necessary to complete this scope of work.
15A  15B  15B  15B  16  16  16  16  16  16  17  17  18  18  18  18  18  18	Tile  Flooring  Flooring  Flooring  Painting	093000  Division 1 096500 096813  Division 1 099113 099123 099600 033511 071900 079200  Division 1 061000 079200 101410	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements Exterior Painting Interior Painting High Performance Coatings Concrete Floor Finishes Water Repellents  Joint Sealants  General Requirements Direct Applied Finish System  General Requirements Rough Carpentry Joint Sealants  Signage Plaques Dimensional Letter Signage	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Pre-Prime all surfaces prior to application of spray texture.  All interior sealants exclusive of glazing, concrete, and millwork.  All sections to be included in their entirety.  All sections to be included in their entirety.  Install backing necessary to complete this scope of work.
15A  15B  15B  15B  15B  16  16  16  16  16  17  17  18  18  18  18  18  18  18  18	Tile  Flooring  Flooring  Flooring  Painting  Painting  Painting  Painting  DEFS DEFS  Specialties	093000  Division 1  096500  096813  Division 1  099113  099123  099600  033511  071900  Division 1  072423  Division 1  061000  079200  Division 1  061000  101410  101416  101419  102113.13  104400	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting Interior Painting High Performance Coatings Concrete Floor Finishes Water Repellents  Joint Sealants  General Requirements Direct Applied Finish System  General Requirements Rough Carpentry Joint Sealants  Signage Plaques Dimensional Letter Signage Metal Toilet Compartments Fire Protection Specialties	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Pre-Prime all surfaces prior to application of spray texture.  All interior sealants exclusive of glazing, concrete, and millwork.  All sections to be included in their entirety.  All sections to be included in their entirety.  Install backing necessary to complete this scope of work.
15A  15B  15B  15B  15B  16  16  16  16  16  16  17  17  18  18  18  18  18  18  18	Tile  Flooring  Flooring  Flooring  Painting  Painting	093000  Division 1 096500 096813  Division 1 099113 099113 099600 033511 071900  Division 1 072423  Division 1 061000 079200 101416 101416 101419 102113.13	Tiling  General Requirements  Resilient Flooring  Tile Carpeting  General Requirements  Exterior Painting Interior Painting High Performance Coatings Concrete Floor Finishes Water Repellents  Joint Sealants  General Requirements Direct Applied Finish System  General Requirements Rough Carpentry Joint Sealants  Signage Plaques Dimensional Letter Signage Metal Toilet Compartments	Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Joint and crack filling, minor leveling, and sanding is included.  Joint and crack filling, minor leveling, and sanding is included.  All sections to be included in their entirety.  Pre-Prime all surfaces prior to application of spray texture.  All interior sealants exclusive of glazing, concrete, and millwork.  All sections to be included in their entirety.  All sections to be included in their entirety.  Install backing necessary to complete this scope of work.

19	Detention Equipment	Division 1	General Requirements	All sections to be included in their entirety.
19	Detention Equipment	111963	Detention Furnishings and Equipment	
19	Detention Equipment	111993	Tamper Resistant Fasteners	
19	Gypsum Board Systems	111950	Detention Ceiling Panel Systems	Addendum 2 - Added to bid package 19
19	Gypsum Board Systems	111951	Detention Ceiling Panel Systems	Addendum 2 - Added to bid package 19
20	Elevators	Division 1	General Requirements	All sections to be included in their entirety.
20	Elevators	142100	Electric Traction Elevators	
20	Elevators	142400	Hydraulic Elevators	
			<u> </u>	
21	Fire Suppression System	Division 1	General Requirements	All sections to be included in their entirety.
				,
21	Fire Suppression System	078400	Firestopping	Limited to penetrations as a result of the work of this package.
21	Fire Suppression System	079200	Joint Sealants	Sealants for this scope of work only.
				Fire line installed to 1'AFF by others. Scope of work includes
21	Fire Suppression System	211313	Fire Sprinkler Systems	being onsite to witness testing of line as required.
22	Plumbing	Division 1	General Requirements	All sections to be included in their entirety.
	i			,
22	Plumbing	078400	Firestopping	Limited to penetrations as a result of the work of this package.
22	Plumbing	079200	Joint Sealants	Sealants for this scope of work only.
22	Plumbing	220513	Common Motor Requirements for Plumbing	
22	Plumbing	220516	Expansion Fittings and Loops for Piping	
22	Plumbing	220517	Sleeves and Sleeve Seals for Plumbing Piping	
22	Plumbing	220519	Meters and Gages for Plumbing Piping	
22	Plumbing	220523	General Duty Valves for Plumbing Piping	
			Hangers and Supports for Plumbing Piping and	
22	Plumbing	220529	Equipment	
			Vibration and Seismic Controls for Plumbing Piping and	
22	Plumbing	220548	Equipment	
22	Plumbing	220553	Identification for Plumbing Piping and Equipment	
22	Plumbing	220719	Plumbing Piping Insulation	
22	Plumbing	221005	Plumbing Piping	
22	Plumbing	221003	Plumbing Piping Specialties	
22	Plumbing	221343	Facility Packaged Sewage Pumping Station	
	Fidilibility	221343	l aciity i ackaged dewage i diriping diation	Tie to compressed air system in existing jail via sleeve. Run
				air lines to air controlled hardware. Connection to hardware
22	Plumbing	221500	General Service Compressed Air Systems	by others.
22		223000		by others.
22	Plumbing		Plumbing Equipment	
	Plumbing	224000	Plumbing Fixtures	
22	Plumbing	224600	Security Plumbing Fixtures	
00	LDVAC	Division 4	0t-	Alltite-le-in-le-dithintite-
23	HVAC	Division 1	General Requirements	All sections to be included in their entirety.
00	10/40	070400		1
23	HVAC	078400	Firestopping	Limited to penetrations as a result of the work of this package.
23	HVAC	079200	Joint Sealants	Sealants for this scope of work only.
23	HVAC	230513	Common Motor Requirements for HVAC	
23	HVAC	230529	Hangers and Supports for HVAC Piping and Equipment	
23	HVAC	230548	Vibration and Seismic Controls for HVAC	
23	HVAC	230593	Testing, Adjusting, and Balancing for HVAC	
23	HVAC	230713	Duct Insulation	
23	HVAC	230719	HVAC Piping Insulation-Airex	
				Owner to retain commissioning agent. Scope of work includes
23	HVAC	230800	Commissioning of HVAC	assisting agent as needed during commissioning process.
23	HVAC	230923	Direct Digital Control System for HVAC	
23	HVAC	230993	Sequence of Operations for HVAC Controls	
23	HVAC	232300	Refrigerant Piping	
23	HVAC	233100	HVAC Ducts and Casings	
23	HVAC	233300	Air Duct Accessories	
23	HVAC	233423	HVAC Power Ventilators	
23	HVAC	233700	Air Outlets and Inlets	
23	HVAC	237416	Packaged Rooftop Air Conditioning Units	
23	HVAC	237433	Dedicated Outdoor Air Units	
23	HVAC	238126.13	Small Capacity Split System Air Conditioners	
24	Electrical Systems	Division 1	General Requirements	All sections to be included in their entirety.
		1		
24	Electrical Systems	078400	Firestopping	Limited to penetrations as a result of the work of this package.
24	Electrical Systems	079200	Joint Sealants	Sealants for this scope of work only.
24	Electrical Systems	260519	Low-Voltage Electrical Power Conductors and Cables	
24	Electrical Systems	260526	Grounding and Bonding for Electrical Systems	
24	Electrical Systems	260529	Hangers and Supports for Electrical Systems	
24	Electrical Systems	260533.13	Conduit for Electrical Systems	
24	Electrical Systems	260533.16	Boxes for Electrical Systems	
24	Electrical Systems	260536	Cable Trays for Electrical Systems	
24	Electrical Systems	260553	Identification for Electrical Systems	
24	Electrical Systems	260573	Power System Studies	
24	Electrical Systems	260583	Wiring Connections	
24	Electrical Systems	260923	Lighting Control Devices	
24	Electrical Systems	262100	Low Voltage Electrical Service Entrance	
24	Electrical Systems	262200	Low Voltage Transformers	
24	Electrical Systems	262413	Switchboards	
24	Electrical Systems	262416	Panelboards	
24	Electrical Systems	262726	Wiring Devices	
24	Electrical Systems	262816.16	Enclosed Switches	
24	Electrical Systems	263213	Engine Generators	
24	Electrical Systems	263600	Transfer Switches	
24	Electrical Systems	264300	Surge Protective Devices	
24	Electrical Systems	265100	Interior Lighting	
24	Electrical Systems	265600	Exterior Lighting	
24	Electrical Systems	270000	Communications	
24	Electrical Systems	281000	Access Control	
	Electrical Systems			
24 24	Electrical Systems Electrical Systems	282100	Video Surveillance Cameras	
24	Electrical Systems			

www.cshqa.com



### **ADDENDUM**

THERON W WARD JUDICIAL BUILDING REMODEL AND EXPANSION 427 Shoshone Street North
Twin Falls, ID 83301

Addendum No. 02 Owner Project Number 21403.000 Date Issued 11 Aug 2023

Original documents signed by the Architect, Danielle Weaver, AIA.



#### 1.1 NOTICE TO BIDDERS

- **A.** This Addendum is issued to the Construction Manager. This Addendum serves to clarify, revise and supersede information in the Project Manual, Drawings and previously issued Addenda.
- B. The Bidder shall acknowledge receipt of this Addendum in the appropriate space on the Bid Form.
- C. Responses to Requests for Information:
  - 1. Question: Can we use Flexible Glass Fiber Blanket Thermal Insulation as specified in section 072100, 2.03, Item A at exterior walls which call for thermal insulation?

Response: Yes. Acoustic Batt Insulation Basis of Design is Owens Corning SAFB, which is Mineral Fiber Blanket Insulation

2. Question: Can we use a Standard 6-mil poly vapor barrier for Spec Section 072100, 2.04 and 072100, 2.05?

Response: In open and semi-concealed insulated spaces requiring a vapor barrier not directly covered by 5/8" type X gypsum board IBC does not allow a poly vapor barrier. Utilize "Foil Scrim-Kraft" as a "radiant barrier insulation material" in these types of spaces. "FSK" is a proprietary term for a Johns-Manville Product. Where Poly Vapor Retarders are allowed, utilize the product specified in 072100, 2.05, Item A.

3. Question: What surface will be selected for the FRP product?

Response: See Material Key Sheet, 181, FRP1.

#### **ADDENDUM**

# THERON W WARD JUDICIAL BUILDING REMODEL AND EXPANSION

#### Addendum No. 02

4. Question: Reference 042200, 2.4, B, 4. Do we really have Sable Ground Face CMU block on this job?

Response: No we do not. Strike this portion of the specification entirely.

5. Question: Reference A50A-3. Are we to install a wood nosing piece in the stairs inside the courtrooms?

Response: Install the finish on these stairs per I81, Material Key, STR1. Provide appropriate transitions between the Carpet floor finish and the STR1 finish.

6. Question: Reference 092116, 2.03, C Abuse Resistant Wallboard. Where is this to be installed?

Response: In the following High Traffic Areas: Vestibule 1.101, Exit Staff Entry 1.105, Security Queuing 1.103, Lobby 1.102, Circulation C106, Circulation C101, Circulation C100, Vestibule D402, Public Circulation C201 and Public Circulation C206.

7. Question: Reference 092116, 3.04, Item B and C Sound Control Putty Pads. Please provide a Manufacturer.

#### Response:

#### Products:

Sound control putty pads:

Sound Transmission Class: Not less than 60,

Surface Burning Characteristics: Flame spread/Smoke developed index of not more than 5/25 maximum, when tested in accordance with ASTM E84.

#### Manufacturers:

- (1) AccoustiGuard Sound and Vibration Control
- (2) Sound Proofing Company.
- (3) Specified Technologies, Inc.

#### Installation:

Sound control putty pads at outlet boxes: Install according to manufacturer's written instructions. Coordinate installation with requirements in Division 26.

#### 1.2 ATTACHMENTS

A. This Addendum includes no attachments.

#### 1.3 REVISIONS TO DIVISIONS 02 - 49 SPECIFICATION SECTIONS

- A. Specification Section 034900 Glass Fiber Reinforced Concrete
  - 1. Paragraph 2.01 Part A Manufacturers
    - Add Wilson Composites LLC Fibertech of Greenville, SC.
- B. Specification Section 087100 Door Hardware
  - Paragraph 2.09 Cylindrical Locks Grade 1, Part 2. Acceptable Manufacturers and Products: Add Sargent Assa Abloy

### **ADDENDUM**

# THERON W WARD JUDICIAL BUILDING REMODEL AND EXPANSION

Addendum No. 02

- C. Specification Section 111950 Detention Ceiling Panel system
  - 1. Paragraph 2.01 Acceptable Manufacturers
    - a. Add: Carritec Product: Arroyo Security Line for DPC3 and Zenith Security Line for DPC1 and DPC1A.

**END OF ADDENDUM** 

August 11, 2023 21403.000 Page 3 of 3

)	ding Renovation/Addition Activity Name	Original	Remaining	Activity % Start	Schedule Sub Finish	2024 2025
	·	Duration	Duration	Complete		Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct
neron W. Ward J	udicial Building Renovation/Addition	699	561	01-Feb-23 A	17-Oct-25	
Preconstruction		187	49	01-Feb-23 A	20-Oct-23	
A1000	Design Complete for Permit & Bidding	100	0	100% 01-Feb-23 A	20-Jun-23 A	Complete for Permit & Bidding
A1060	Procurement Items	90	0	100% 01-Feb-23 A		nent Items
A1030	Obtain Building Permit	1	0	100% 21-Jun-23 A		Building Permit
A1010	Create Bid Packages	10	0	100% 10-Jul-23 A	21-Jul-23 A	reate Bid Packages
A1020	Bidding	20	9	55% 24-Jul-23 A	24-Aug-23	Bidding
A1040	Contracting	10	10	0% 25-Aug-23	08-Sep-23	Contracting
A1070	SWPPP Installation	2	2	0% 05-Sep-23*	06-Sep-23	I SWPPP Installation
A1050	Submittals	30	30	0% 11-Sep-23	20-Oct-23	Submittals
Construction	Odbrillidas	529	529	07-Sep-23	26-Sep-25	
		020	020		-	
General		4	4	07-Sep-23	12-Sep-23	
A1080	Job Trailer Relocation	1	1	0% 07-Sep-23*	07-Sep-23	I Job Trailer Relocation
A1090	Temporary Fencing/Security Set-Up	3	3	0% 08-Sep-23	12-Sep-23	Temporary Fencing/Security Set-Up  Temporary Fencing/Security Set-Up  Temporary Fencing/Security Set-Up
A1100	Existing Sign/Structure Protection	1	1	0% 08-Sep-23	08-Sep-23	I Existing Sign/Structure Protection
Site Work		350	350	08-Sep-23	21-Jan-25	
Demolition	To a color of the	23	23	13-Sep-23	13-Oct-23	I Trace/Charles
A1110	Trees/Shrubs	1	1	0% 13-Sep-23	13-Sep-23	I Trees/Shrubs
A1120	Landscaping Curb	2	2	0% 13-Sep-23	14-Sep-23	I Landscaping Curb
A1130	Sidewalks	5	5	0% 13-Sep-23	19-Sep-23	□ Sidewalks
A1140	Light Pole/Associated Appearances	2	2	0% 13-Sep-23	14-Sep-23	I Light Pole/Associated Appearances
A1150	Jail Perimeter Fence	5	5	0% 13-Sep-23	19-Sep-23	■ Jail Perimeter Fence
A1160	Swale with Drainage Window	5	5	0% 20-Sep-23	26-Sep-23	■ Swale with Drainage Window
A1170	Existing Sidewalk, Curb, & Gutter (New Water & Fire I	8	8	0% 04-Oct-23	13-Oct-23	☐ Existing Sidewalk, Curb, & Gutter (New Water & Fire Protection Service Connection)
A1180	Existing Sidewalk, Curb, & Gutter (New 6" Sewer Line	3	3	0% 04-Oct-23	06-Oct-23	Existing Sidewalk, Curb, & Gutter (New 6" Sewer Line & Manholes)
Utilities	Verify Oran English Others David Leading	36	36	08-Sep-23	27-Oct-23	1. Vá vite / Constituto Cividatio Come Dunio II positivo
A1190	Varify/Confirm Existin Storm Drain Location	1	1	0% 08-Sep-23	08-Sep-23	I Varify/Confirm Existin Storm Drain Location
A1200	Varify/Confirm Location & Depth of existing Sanitary S	1	1	0% 08-Sep-23	08-Sep-23	I Varify/Confirm Location & Depth of existing Sanitary Sewer Line
A1210	Demo Existing Sanitary Sewer Line (Jud. Bldg. to Jail	5	5	0% 27-Sep-23	03-Oct-23	Demo Existing Sanitary Sewer Line (Jud. Bldg. to Jail)
A1230	Connect new 6" & 8" SDR 35 Sanitary Sewer Service	10	10	0% 09-Oct-23	20-Oct-23	Connect new 6" & 8" SDR 35 Sanitary Sewer Service
A1270	Install 1,000 gal. Sand and Grease Trap	3	3	0% 09-Oct-23	11-Oct-23	I Install 1,000 gal. Sand and Grease Trap
A1280	Install Rainstorms	2	2	0% 12-Oct-23	13-Oct-23	I Install Rainstorms
A1220	Connect new 6" Fire Service to Existing Main	10	10	0% 16-Oct-23	27-Oct-23	☐ Connect new 6" Fire Service to Existing Main
A1240	Install Manholes	2	2	0% 23-Oct-23	24-Oct-23	I Install Manholes
A1250	Install 8"x8" Nyoplast Downspout Adapter	2	2	0% 23-Oct-23	24-Oct-23	I Install 8"x8" Nyoplast Downspout Adapter
A1260	Install ACO K1 Endcap on Existing Trench Drain	2	2	0% 23-Oct-23	24-Oct-23	I Install ACO K1 Endcap on Existing Trench Drain
Grading/Landsca		332	332	04-Oct-23	21-Jan-25	
A1290	Clear and Grub Site Top Soil	3	3	0% 04-Oct-23	06-Oct-23	Clear and Grub Site Top Soil
A3320	Concrete Sidewalk & Stairs	10	10	0% 30-Dec-24	10-Jan-25	Concrete Sidewalk & Stairs
A3340	New Security Fence	10	10	0% 30-Dec-24	10-Jan-25	□ New Security Fence
A3350	4"x4" Painted Automatic Door Tube	5	5	0% 30-Dec-24	03-Jan-25	4"x4" Painted Automatic Door Tube
A3360	Cast-In-Place Planters	5	5	0% 30-Dec-24	03-Jan-25	Cast-In-Place Planters
A3330	Stainless Steel Handrail Assembly	2	2	0% 13-Jan-25	14-Jan-25	I Stainless Steel Handrail Assembly
A3370	Site/Landscape Punchlist	5	5	0% 15-Jan-25	21-Jan-25	□ Site/Landscape Punchlist
Building A Demolit		48	48	09-Oct-23	14-Dec-23	<del>-</del>
A1300	Remove Owners Items	2	2	0% 09-Oct-23	10-Oct-23	I Remove Owners Items
A1310	Install Temporary Dust Partition	1	1	0% 11-Oct-23	11-Oct-23	I Install Temporary Dust Partition
A1320	Electrical Demolition	10	10	0% 12-Oct-23	25-Oct-23	□ Electrical Demolition
Actual Work	♦ Milestone			Page 1 of 6		ate Revision Checked Approved
Remaining Work				g- · -· <del>v</del>	31-Jul-2	23 Schedule JD JD
Critical Remaining W	ork					STAND I
5			1		1	

Theron	W. Ward Judicial Build	ding Renovation/Addition					Schedule Su	bject to Change															16- <i>A</i>	Aug-23 (	09:35
Activity ID		Activity Name	Original	Remaining	Activity %	Start	Finish					'	2024									2025			
			Duration	Duration	Complete			Aug Sep Oct Nov Dec				Apr May	Jun Ju	I Aug	Sep Oct	: Nov [	Dec .	Jan	Feb N	/lar Ap	r May	Jun Ju	I Aug S	ep Oct	t Nov
	A1330	Mechanical Demolition	10	10	0%	12-Oct-23	25-Oct-23	■ Mechani																	
	A1340	Plumbing Demolition	10	10	0%	12-Oct-23	25-Oct-23	☐ Plumbing	) De	molition	<u> </u>		:								. !				
	A1350	Demo Interior Doors, Windows, Walls	5	5	0%	26-Oct-23	01-Nov-23	■ Demo li	nter	ior Door	rs, Win	dows, Wall	s							;					
	A1360	Demo Floor	5	5	0%	02-Nov-23	08-Nov-23	☐ Demo	Floo	or			1						- 1	-	!				
	A1370	Demo Roof Structure	10	10	0%	09-Nov-23	22-Nov-23	□ Den	no F	Roof Str	ucture														
	A1380	Demo Exterior Walls & Doors	10	10	0%	24-Nov-23	07-Dec-23	D	)emo	o Exteri	ior Walls	s & Doors	1								1				-
	A1390	Cut and Remove Existing Concrete Slab/Foundation	5	5	0%	08-Dec-23	14-Dec-23		Çut	and Re	move E	Existing Co	ncrete S	Slab/Fo	ındation										
	<b>Building B Additio</b>		315	315		04-Oct-23	27-Dec-24				]		1	[]											
	Structure/Exterior		315	315		04-Oct-23	27-Dec-24						1												
	A1400	Excavate for Basement Footings	8	8	0%	04-Oct-23	13-Oct-23	Excavate for	or B	asemer	nt Footi	ngs	1												
	A1410	Basement Footings	10	10	0%	16-Oct-23	27-Oct-23	■ Baseme	nt F	ootings	\$							i		;					
	A1420	Basement Concrete Walls West	15	15	0%	30-Oct-23	17-Nov-23	Base	mei	nt Conc	crete W	alls West	:							!					1
	A1430	Basement Concrete Walls East	15	15	0%	20-Nov-23	11-Dec-23	The state of the s	Base	ement C	Concret	e Walls Ea	st												
	A1440	Basement West Elevator/Stair Core CMU Walls	20	20	0%	20-Nov-23	18-Dec-23		Bas	sement	West E	levator/Sta	air Core	CMU V	/alls					!					1
	A1450	Basement East Elevator/Stair Core CMU Walls	15	15	0%	12-Dec-23	03-Jan-24		i E	3aseme	ent Eas	t Elevator/s	Stair Co	re CMU	Walls		i	į		;					
	A1480	Backfill Around Basement Walls	5	5		12-Dec-23	18-Dec-23		Bac	ckfill Aro	und Ba	sement W	alls							!					
	A1460	Basement Underground Plumbing Rough In	5	5		12-Dec-23	18-Dec-23	—H : : : : :		- 1	1 1	ground Plu		Rouah İ	n :										
	A1490	Gravel Building Pad	5	5		19-Dec-23	26-Dec-23			ravel B	313									<u> </u>					
	A1470	Basement Underground Electrical Rough In	3	3		19-Dec-23	21-Dec-23			1 1	1 7	ground Ele	: ectrical F	Rough I	n :										
	A1500	Excavate for 1st Floor Building Footings	5	5		27-Dec-23	03-Jan-24					st Floor Bu						- 1	- 1	-	1				
	A1510	1st Floor Footings/Foundations	20	20		29-Dec-23	26-Jan-24				1 1	ootings/For	T	1 - 1											
	A1510	1st Floor Underground Plumbing Rough In	10	10		15-Jan-24	26-Jan-24		T			ndergroun			ıah İn			- 1	-	1	1				
	A1540	1st Floor Underground Electrical Rough In	10	10		22-Jan-24	02-Feb-24			L	1	Jndergrou		L				·							
				5		29-Jan-24	02-Feb-24 02-Feb-24		1		1 1	_obby Elev	1	1 1	- 1	lle.					1				
	A1520	1st Floor Lobby Elevator/Stair Core CMU Walls	5	50						15	i LIOOI I	Steel Stru			CIVIŲ VVA	1115									
	A1550	Steel Structure Erection	50	50		29-Jan-24	05-Apr-24				1 1	i i	i	i i	alcin d					1	1				
	A1570	1st Floor Joists and Decking	5	5		08-Apr-24	12-Apr-24				! !'	I 1st Floo ■ Basem			_	_				1					
	A1580	Basement Slab on Grade Pour	5	5		15-Apr-24	19-Apr-24										<del> </del> -	<del> </del>							
	A1600	2nd Floor Joist and Decking	10	10		15-Apr-24	26-Apr-24					2nd F	1	1 1	, •					1					
	A1610	1st Floor Concrete Floor Pour	5	5		29-Apr-24	03-May-24								Floor Pou	ır		i		1					
	A1630	Roof Joist and Decking	10	10		29-Apr-24	10-May-24					1 1	of Joist	1 1	۳,					!					
	A1560	Basement Stair Erection	2	2		13-May-24	14-May-24		-			i i	asement	- 1 - 1	- ;	_		- 1	-	1					
	A1640	2nd Floor Concrete Floor Pour	5	5		13-May-24								L	te Floor	_ L									
	A1650	Exterior Metal Stud Framing	20	20		13-May-24	10-Jun-24		-			i i	i	i i	I Stud Fr	aming				1	1				
	A1590	1st Floor Stair Erection	3	3		15-May-24	17-May-24						st Floor :												
	A1620	2nd Floor Stair Erection	3	3		20-May-24	22-May-24						2nd Floo	1 1	1					1	1				
	A1880	Concrete Stair Pours	15	15		23-May-24	13-Jun-24					: :	:		air Pours										
	A1660	Exterior Sheathing	10	10	0%	04-Jun-24	17-Jun-24		. j		ji.		<b>E</b> xte					<u>.</u> .				i			
	A1670	Exterior Weather Barrier	10	10	0%	11-Jun-24	24-Jun-24						■ Ext	terior W	eather B	arrier				1					
	A1680	Exterior Masonry & CMU	90	90		18-Jun-24	23-Oct-24						1	! !	1	Exterio		1-			1				
	A1690	Exterior Window Aluminium Frames	20	20	0%	21-Aug-24	18-Sep-24						1		Exte	rior Win	dow A	Alumi	inium F	rames					
	A1700	Exterior Glazing	30	30	0%	24-Oct-24	05-Dec-24		-				1 1 1			$\dot{-}$	Exte	erior (	Glazin	g					
	A1710	Parapet Cap	5	5	0%	24-Oct-24	30-Oct-24						1			■ Para <sub>l</sub>	pet C	Сар 🗄			!				
	A1720	GFRC Exterior Panels	10	10	0%	24-Oct-24	06-Nov-24									GFF	RC Ex	xterio	r Pane	els					
	A1730	Exterior Pliaster Column Wraps	20	20	0%	07-Nov-24	05-Dec-24						:				Exte	erior	Pliaste	r Colun	n Wra	os			
	A3430	Exterior Light Fixtures	5	5		07-Nov-24	13-Nov-24		į				į			■ Ex	terior	Ligh	t Fixtur	res					
	A1740	Exterior Doors	10	10		06-Dec-24	19-Dec-24						1		:	1 1	1	٠,	or Doo	1	1				
	A1750	Exterior Punchlist	5	5		20-Dec-24	27-Dec-24		į		1 1		1		i					nchlist	: : :				1
	Finishes/Interior		172	172		22-Apr-24	23-Dec-24	<b>1</b>					<u>+</u>					·							
									-						•		-	-							
	Actual Work	♦ Milestone			Door	e 2 of 6	[	Date R	evisio	on		Chec	cked	Approve	d						A				
	Remaining Work	V TIMOSOTIO			Page	5 Z UI Ü	31-Jul	-23 Schedule				JD		D							Cor	t .			
	<ul><li>Critical Remaining W</li></ul>	ork																		Stan	1				
	- Chican Chaining W	<u> </u>																							

Theron W.	Ward Judicial Buil	lding Renovation/Addition					Schedule Su	bject to Change											16-	Aug-23 09:35
Activity ID		Activity Name		Remaining	Activity %	Start	Finish						2024				202	5		
			Duration	Duration	Complete			Aug Sep Od	t Nov Dec	Jan Feb N	Mar Apr Ma	1ay J	Jun Jul Aug	Sep Oc	t Nov Dec Jan	Feb Mar	Apr May Jun	Jul	Aug S	ep Oct Nov
	A1760	Staff Elevators	35	35	0%	20-Jun-24	08-Aug-24							Staff Eleva	1 1 1					
	A1770	Detention Elevators	40	40	0%	09-Aug-24	04-Oct-24							1 1	Detention Elevator	1 1				
	A1780	Lobby Elevators	30	30		07-Oct-24	15-Nov-24								Lobby Elev	ators				
	Basement		63	63		22-Apr-24	19-Jul-24							ļļ		ļ ļ				
	A1790	Masonry CMU Walls	20	20		22-Apr-24	17-May-24				1 1		lasonry CMU							
	A1800	Metal Stud Wall Framing	10	10		22-Apr-24	03-May-24				: :	- :	al Stud Wall Fr	: •:						
	A1820	Mechanical Rough In	15	15		06-May-24	24-May-24				1 1		Mechanical Ro	, •					!	
	A1830	Plumbing Rough In	10	10		20-May-24	03-Jun-24				and the second second		Plumbing Ro	. •					į	
	A1840	Electrical Rough In	10	10		20-May-24	03-Jun-24					'	Electrical Ro	_'		¦				
	A1810	Fire Sprinkler Rough In	10	10		20-May-24	03-Jun-24				1 1		Fire Sprinkle	. 7	1					
	A1850	Fire Alarm Rough In	5	5		20-May-24	24-May-24					- :	ire Alarm Rou	7						
	A1860	Security Rough In	5	5		20-May-24	24-May-24				1 1		Security Roug						:	
	A1870	Telecom Rough In	5	5		20-May-24	24-May-24						Telecom Roug							
	A1890	Wall Insulation	3	3		04-Jun-24	06-Jun-24			·		'	Wall Insulati			¦				
	A1900	Gypsum Walls (HTT)	5	5		07-Jun-24	13-Jun-24	_					☐ Gypsum V		1 1 1					
	A1910	Gypsum Ceilings (HTT)	2	2		14-Jun-24	17-Jun-24						I Gypsum (	Cellings (H	11)					
	A1920	Paint	2	2		18-Jun-24	19-Jun-24						I Paint							
	A1930	Steel Security Ceiling Assembly	3	3		20-Jun-24	24-Jun-24	_					1 1		ng Assembly				!	
	A1940	Polished Concrete Floors	5	5		25-Jun-24	01-Jul-24							d Concrete		ļļ				
	A1950	Fire Sprinkler Trim	2	2		02-Jul-24	03-Jul-24							rinkler Trim	1					
	A1960	Mechanical Trim	3	3		02-Jul-24	05-Jul-24	_					: :	nical Trim						
	A1970	Plumbing Trim	2	2		02-Jul-24	03-Jul-24	_				i	l Plumbir	Ψ ,	1.11-41				į	
	A1980	Electrical Trim & Lighting	3	3		02-Jul-24	05-Jul-24	_					i i	al Trim & L	Ignung					
	A1990	Fire Alarm Trim	2	2		02-Jul-24	03-Jul-24						I Fire Ala			ļ	-}			
	A2000	Security Trim	2	2		02-Jul-24	03-Jul-24	_					I Securit							
	A2010	Telecom Trim	2	2		02-Jul-24	03-Jul-24	-					□ Doors	1 1						
	A2060	Doors & Hardware	5	5		02-Jul-24	09-Jul-24	_					1 1	о пацима eiling Tiles	are .				-	
	A2020	Set Ceiling Tiles	2	2		08-Jul-24	09-Jul-24						I Gun I	. •						
	A2030	Gun Lockers Bathroom Accessories	2	2		10-Jul-24	11-Jul-24							oom Acce		ļ				
	A2040		3	3		10-Jul-24 10-Jul-24	12-Jul-24	_					1 1	etention Be	The state of the s					
	A2050 A2070	SS Detention Benches Basement Punchlist	2	5		15-Jul-24	11-Jul-24 19-Jul-24	$-\parallel$				i i	: :	ement Pur						
	1st Floor	Dasement Functilist	142	142		06-May-24	22-Nov-24						l Dase	inenti ui	ICI IIISC					
	A2090	Metal Stud Wall Framing	15	15		06-May-24 06-May-24	24-May-24	-				<b>-</b> ! \	Metal Stud Wa	ll Framing						
	A2080	Masonry CMU Walls	20	20		20-May-24	17-Jun-24						■ Masonry (			<del>  </del>				
	A2120	Composite Raised Floor Framing	20	20		28-May-24	24-Jun-24					Ė		1 1	Floor Framing					
	A2130	Court Room Floor Assembly Framing	10	10		28-May-24	10-Jun-24					ė	1 17		sembly Framing					
	A2150	Mechanical Rough In	20	20		28-May-24	24-Jun-24					Ė	Mechani	1 1						
	A2160	Plumbing Rough In	20	20		28-May-24	24-Jun-24					ė	Plumbing							
	A2170	Electrical Rough In	20	20		28-May-24	24-Jun-24					· · · · ·	Electrical	' <b>T</b>						
	A2140	Fire Sprinkler Rough In	15	15		28-May-24	17-Jun-24					Ė	Fire Sprinl	der Rough	ıln					
	A2180	Fire Alarm Rough In	10	10		28-May-24	10-Jun-24					Ė	Fire Alarm F	Rough In						
	A2190	Security Rough In	10	10		28-May-24	10-Jun-24					ė	Security Ro	ugh In						
	A2200	Telecom Rough In	10	10		28-May-24	10-Jun-24					Ė	■ Telecom Ro	ough In					į	
	A2100	Ceiling Framing	10	10		25-Jun-24	09-Jul-24						Ceiling	Framing						
	A2220	Wall Insulation	5	5		25-Jun-24	01-Jul-24						■ Wall Ins						!	
	A2230	Gypsum Walls (HTT)	20	20	0%	27-Jun-24	25-Jul-24						Gy <sub> </sub>	sum Wall	s (HTT)					
	A2110	Soffit Framing	5	5	0%	10-Jul-24	16-Jul-24						■ Soffit	Framing					-	
										<u> </u>	·		· · · · · · · · · · · · · · · · · · ·				· · · · · · · · · · · · · · · · · · ·			·
	Actual Work	◆ Milestone			Page	e 3 of 6		Date		evision		Chec		ved			A .			
F	Remaining Work				9		31-Ju	-23 Sched	ule		JD	)	JD				Cost			
	Critical Remaining W	/ork														9	>16.0			
							<u> </u>													

Theron W	V. Ward Judicial Buil	ding Renovation/Addition					Schedule Su	bject to C	Change																	16-Aug	g-23 09:	:35
Activity ID		Activity Name		Remaining	Activity %	Start	Finish								024									2025				
			Duration	Duration	Complete			Aug S	ep Oct No	ov Dec	Jan F	eb Mar	Apr M	1ay Jun	Jul	Aug S	ep O	t Nov	Dec	Jan	Feb	Mar A	pr May	Jun	Jul A	ug Sep	Oct	Nov
	A2240	Gypsum Ceilings (HTT)	15	15	0%	19-Jul-24	08-Aug-24										sum C				+				- 1			
	A2250	Paint	5	5	0%	09-Aug-24	15-Aug-24									■ Pa	int ¦					,						
	A2260	Steel Security Ceiling Assembly	10	10	0%	16-Aug-24	29-Aug-24										Steel S	ecurity	Ceilir	ng Ass	sembl	y						
	A2270	ACT Ceiling Sytem	10	10	0%	16-Aug-24	29-Aug-24					į		i			ACT C	eiling S	ytem	į		, i	i		į	}		
	A2330	Millwork	20	20	0%	16-Aug-24	13-Sep-24					- 1				Ė	Millw	ork	1				!		1			
	A2280	Polished Concrete Floors	3	3		30-Aug-24	04-Sep-24					i		į		į.	Polish	ed Co	crete	∍Floo	ırs		į		i !			
	A2290	Walk Off Carpet	3	3		05-Sep-24	09-Sep-24	11								0	Walk	Off Ca	rpet									
	A2300	Sheet Vinyl Flooring	8	8		16-Sep-24	25-Sep-24					- 1					■ Sh	neet Vir	ıyl Flc	oring	1	į	i !		1 1			
	A2310	Carpet Flooring (all types 1-4)	20	20		16-Sep-24	11-Oct-24											Carpe	t Floo	ring (	all typ	es 1-4)			1			
	A2320	Floor Tile (all types 1-2)	5	5		16-Sep-24	20-Sep-24					- 1		-			■ Flo						1		1 1 1			
	A2420	Bathroom Accessories	5	5		26-Sep-24	02-Oct-24											Bathroc										
	A2340	Fire Sprinkler Trim	5	5		14-Oct-24	18-Oct-24								± L ! !			Fire S	Sprink	der Tr	im							
	A2350	Mechanical Trim	10	10		14-Oct-24	25-Oct-24										- 1	Med	;-	i	i i				į			
	A2360	Plumbing Trim	10	10		14-Oct-24	25-Oct-24											Plur	nbina	Trim			!		-			
	A2370	Electrical Trim & Lighting	10	10		14-Oct-24	25-Oct-24					į				į	i	i		1	& Ligh	tina	į		į			
	A2380	Fire Alarm Trim	5	5		14-Oct-24	18-Oct-24					- 1						Fire A					!					
	A2390	Security Trim	5	5		14-Oct-24	18-Oct-24				j		- <del> </del>		i			Secu	ıritv Tr	rim								
	A2400	Telecom Trim	5	5		14-Oct-24	18-Oct-24	$\exists \sqcup$				- 1						1	om Tr	:			1		1			
	A2430	Doors & Hardware	5	5		14-Oct-24	18-Oct-24	$-\parallel$				-				i		Door	1	1	/are	i	i		i !	Ì		
	A2450	Courtroom Chair Rail	5	5		14-Oct-24	18-Oct-24	$\exists \sqcup$									i	Cour	i	i	i i		1		1	}		
	A2410	Set Ceiling Tiles	10	10		28-Oct-24	08-Nov-24					1		-		-	-	1	į.	eiling T		į	1		1	-		
	A2410 A2440	Courtroom TV Monitors	5	5		11-Nov-24	15-Nov-24												-1		- 4 4	lonitors						
	A2460	Courtroom Mobile Witness Stand	5	5		11-Nov-24	15-Nov-24	-				- 1							1			le Witnes	ee Stan	d	1 1 1			
	A2400 A2470	SS Detention Benches	5	5		11-Nov-24	15-Nov-24	$-\parallel$										1	1	1	ion Be		SSICIAIT	<b>u</b>	1			
	A2470 A2480	1st Floor Punchlist	5	5		18-Nov-24	22-Nov-24	$-\parallel$										i	i	i	Punch	i i			1			
	2nd Floor	13t 1 DOI 1 UTICITISt	147	147		28-May-24	23-Dec-24					į		i		i		-   -	1301	10011	union	list			i	}		
	A2500	Metal Stud Wall Framing	15	15		28-May-24	17-Jun-24								Metal S	Stud W	all Fran	nina						1				
	A2490	Masonry CMU Walls	20	20		18-Jun-24	16-Jul-24	$-\parallel$				i			<u> </u>			, –		į		į	i		i !	Ì		
	A2530	Composite Raised Floor Framing	20	20		18-Jun-24	16-Jul-24	$\exists \sqcup$							i i	i '	site Rai	i	or Fr	amino	a							
	A2540	Court Room Floor Assembly Framing	10	10		18-Jun-24	01-Jul-24	-									m Floo				-				1			
	A2550	Fire Sprinkler Rough In	15	15		18-Jun-24	09-Jul-24	$-\parallel$							1 1	1	ıkler Ro	1			9				į			
	A2590	Fire Alarm Rough In	10	10		18-Jun-24	01-Jul-24				ii		· <del> </del> <del> </del>		Fire					i		:		1			††	
	A2600	Security Rough In	10	10		18-Jun-24	01-Jul-24	$-\parallel$				į			Seci		, 0	1		į					i	}		
	A2610	Telecom Rough In	10	10		18-Jun-24	01-Jul-24	$\exists \sqcup$							Tele								1		1	}		
	A2560	Mechanical Rough In	20	20		25-Jun-24	23-Jul-24					i					nical R		m	į		į	i		i !	Ì		
	A2570	Plumbing Rough In	20	20		25-Jun-24	23-Jul-24	-							1 1	1	ng Roi	, •	1						1			
	A2580	Electrical Rough In	20	20		25-Jun-24	23-Jul-24								·		al Rou							1	·   !			
	A2510	Ceiling Framing	10	10		24-Jul-24	06-Aug-24	$-\parallel$						-	1		ng Frai	- 1							į			
	A2630	Wall Insulation	5	5		24-Jul-24	30-Jul-24	-		1					1 1		nsulatio		1			1	1 1 1		!			
	A2640	Gypsum Walls (HTT)	20	20		26-Jul-24	22-Aug-24	$-\parallel$				į			1 1		Sypsum		HTT	1					į			
	A2520	Soffit Framing	5	5		07-Aug-24	13-Aug-24	$-\parallel$							1 1		ffit Fran	1	,,,,,	<b>'</b>			!		-			
			15												<del></del>		Gyps		ilinge	, LITT	أأ	, <del> </del>		ii			· <del> </del> <del> </del> -	
	A2650	Gypsum Ceilings (HTT)		15		16-Aug-24	06-Sep-24	-									Gyps Pain		illigs	(1111)	4		!		-			
	A2660	Paint Steel See with Calling Assembly	5	5		09-Sep-24	13-Sep-24	$-\parallel \parallel \parallel$				i		į					ourit.	Coilin	ng Ass	ombk.	į		i !			
	A2670	Steel Security Ceiling Assembly	10	10		16-Sep-24	27-Sep-24	$-\parallel$		1												=HIDIY	1 1 1		1	}		
	A2680	ACT Ceiling Sytem	10	10		16-Sep-24	27-Sep-24	$-\parallel$						i				CT Cei Millwo	,	ytern			1 1 1				1 1	
	A2730	Millwork	20	20		16-Sep-24	11-Oct-24				ļ				<del></del>					heat.								
	A2690	Polished Concrete Floors	3	3		30-Sep-24	02-Oct-24	$-\parallel$		!						i	1	1	1	1	Floor	5	1				1 1	
	A2700	Sheet Vinyl Flooring	8	8	0%	14-Oct-24	23-Oct-24			1			<u> </u>		<u> </u>			She	∌ι vin'	yı rıo	oring			<u> </u>	!	!	<u> </u>	
	A - 6 13 A / - 1	A MIL :					r	Date		Re	vision			Checked	Δr	proved	1						A					$\dashv$
	Actual Work	◆ Milestone			Page	e 4 of 6	31-Jul		Schedule	1.0			JE		JD	p.0 100	$\dashv$						And	dr				
	Remaining Work																					CTA	No Co	71				
	Critical Remaining W	ork															$\neg$					700						

vv. vvard Judiciai i	Building Renovation/Addition	1 0	<u> </u>	A - #: # 0/   C: 1	<u> </u>	ubject to Change		000	4		222		ıg-23 0
	Activity Name	Original F	Remaining Duration	Activity % Start Complete	Finish		1. 11	202		0.11.15	2025		10.
10710	0 15 1 ( 100)			•	24 22 11 2		ec Jan Feb Mar	Apr May Jun	Jul Aug Sep	Oct Nov Dec Jan Feb		Jul Aug Sep	Oct
A2710		20	20	0% 14-Oct-						Carpet Flooring (t			
A2720	( ); /	5	5	0% 14-Oct-						☐ Floor Tile (all types 1-2	and the second s		
A2820		5	5	0% 24-Oct-						■ Bathroom Accessor			
A2740	•	5	5	0% 11-Nov						Fire Sprinkler Trir	i i i		
A2750	Mechanical Trim	10	10	0% 11-Nov	24 22-Nov-2					Mechanical Trin	ו		
A2760	Plumbing Trim	10	10	0% 11-Nov	24 22-Nov-2					Plumbing Trim			
A2770	Electrical Trim & Lighting	10	10	0% 11-Nov	24 22-Nov-2					Electrical Trim &	Lighting		
A2780	Fire Alarm Trim	5	5	0% 11-Nov	24 15-Nov-2					■ Fire Alarm Trim			
A2790		5	5	0% 11-Nov	24 15-Nov-2					Security Trim			
A2800	Ţ.	5	5	0% 11-Nov						■ Telecom Trim			į
A2830		5	5	0% 11-Nov						Doors & Hardwa	re		
A2850		5	5	0% 11-Nov						□ Courtroom Chair	i i i		
A2830 A2810		10	10	0% 11-Nov						Set Ceiling T			į
	9									Courtroom			
A2840		5	5	0% 10-Dec		$-$ II $\parallel$ $\parallel$ $\parallel$ $\parallel$					i i i		
A2860		5	5	0% 10-Dec							Mobile Witness Star	ıq	
A2870		5	5	0% 10-Dec						■ \$S Detention	1 1 1		
A2880		5	5	0% 17-Dec						■ 2nd Floor	Punchlist		
Building A Dem	nolition (Phase 2)	51	51	24-Dec	24 05-Mar-2								
A2890	Remove Owners Items	10	10	0% 24-Dec	24 07-Jan-2						e Owners Items		
A2900	Temporary Dust Partition	1	1	0% 08-Jan-	25 08-Jan-2					l Tempor	ary Dust Partition		
A2920	Electrical Demolition	10	10	0% 09-Jan-	25 22-Jan-2					■ Elect	rical Demolition		
A2930	Mechanical Demolition	10	10	0% 09-Jan-						■ Mecl	nanical Demolition		
A2940	Plumbing Demolition	10	10	0% 09-Jan-						■ Plum	bing Demolition		
A2910	Demo Existing Entry Structure	10	10	0% 09-Jan-							o Existing Entry Stru	cture	
A2950	Demo Doors, Windows, Walls	20	20	0% 23-Jan-							Demo Doors, Windo		
		10	10								emo Existing Mezzar		
A2960	Demo Existing Mezzanine Floor			0% 23-Jan-		_					Demo Floor	ili le FiQOI	
A2970	Demo Floor	10	10	0% 13-Feb								/D   1   1   1	
A2980	Demolition Cleanup/Punchlist	5	5	0% 27-Feb							Demolition Clean	up/Punchiist	
Renovation Bu		147	147	06-Mar									
A2990	Metal Stud Wall Framing	20	20	0% 06-Mar	-						Metal Stud V	1 0	
A3000	Frame Ceilings	10	10	0% 03-Apr-							Frame Ce	, •	-
A3030	Mechanical Rough In	20	20	0% 03-Apr-	25 30-Apr-25						1 1 1	nical Rough In	
A3040	Plumbing Rough In	20	20	0% 03-Apr-	25 30-Apr-25						Plumbir	ig Rough In	
A3050	Electrical Rough In	20	20	0% 03-Apr-	25 30-Apr-25						Electrica	al Rough In	
A3020	Fire Sprinkler Rough In	15	15	0% 03-Apr-	25 23-Apr-25						Fire Sprir	ıkler Rough In	
A3060	Fire Alarm Rough In	10	10	0% 03-Apr-							Fire Alarm	Rough In	
A3070	Security Rough In	10	10	0% 03-Apr-							Security R	ough In	
A3080	Telecom Rough In	10	10	0% 03-Apr-	· ·						■ Telecom R		
A3010	Frame Soffits	10	10	0% 17-Apr-							☐ Frame \$		
A3090	Inspections	3	3	0% 01-May							■ Inspec	i i i	-
A3100	Wall Insulation	10	10	0% 01-May								Insulation	
											1 1 1	Gypsum Walls (F	_; 
A3110	Gypsum Walls (HTT)	20	20	0% 15-May		-					: : :		: 1
A3120	Gypsum Ceilings (HTT)	15	15	0% 05-Jun-								Gypsum Ceilin	igs (F
A3130	Paint	5	5	0% 23-Jun-								Paint	
A3140	ACT Ceiling Sytem	20	20	0% 30-Jun-								ACT Ceili	
A3150	Polished Concrete Floors	3	3	0% 28-Jul-2								I Polished	
A3170	Sheet Vinyl Flooring	8	8	0% 28-Jul-2	5 06-Aug-2							□ Sheet \	
A3180	Carpet Flooring (all types 1-4)	20	20	0% 28-Jul-2	5 22-Aug-2						1 1 1 1 1 1 1 1 1	Car	pet Fl
Actual Work	◆ Milestone			Page 5 of 6		Date	Revision	Checked	Approved		<b>A</b>		
Remaining Work				raye 3 01 0	31-	ıl-23 Schedule		JD	JD		Cost		
Critical Remainin											Starr		
• Cuicai Kemainin	IQ VVOIK		1								1		

Theron \	W. Ward Judicial Bu	ilding Renovation/Addition				Schedule Sub	ject to Ch	ange										16-A	Aug-23 (	)9:35									
Activity ID		Activity Name	Original Duration	Remaining Duration	Activity % Start Complete	Finish	Aug Se	p Oct	Nov De	ec Jan	Feb N	∕lar Ap	or May		Jul	Aug	Sep	Oct	Nov	Dec	Jan	eb Ma	ar Apr	May .	2025 Jun J	lul Au	ug S∈	ep Oct	Nov
	A3190	Floor Tile (all types 1-2)	5	5	0% 28-Jul-25	01-Aug-25										-												Tile (all	
	A3160	Walk Off Carpet	3	3	0% 31-Jul-25	04-Aug-25		1 1	į			į	į	İ						i	i			1 1	i	<b>□</b> \	<i>N</i> alk (	Off Car	pet
	A3290	Bathroom Accessories	5	5	0% 07-Aug-25	13-Aug-25									! ! !												Bath	hroom	Acces
	A3200	Millwork	20	20	0% 11-Aug-25	05-Sep-25						!	!		!												<u> </u>	Millwor	K
	A3210	Fire Sprinkler Trim	5	5	0% 25-Aug-25	29-Aug-25		_ii				<u>.</u>		L	<u>.</u>					j	<u>i</u>			<u> </u>			0 Fi	ire Spr	nkler
	A3220	Mechanical Trim	10	10	0% 25-Aug-25	05-Sep-25									,												<u> </u>	Mecha	nical
	A3230	Plumbing Trim	10	10	0% 25-Aug-25	05-Sep-25						į															i 📮 [	Plumbi	ng Tr
	A3240	Electrical Trim & Lighting	10	10	0% 25-Aug-25	05-Sep-25																					_ <b>i</b> _	Electric	;al Tri
	A3250	Fire Alarm Trim	5	5	0% 25-Aug-25	29-Aug-25						1			1												■ Fi	ire Alar	m Tri
	A3260	Security Trim	5	5	0% 25-Aug-25	29-Aug-25		<u> </u>				<u>.</u>		j.	<u> </u>					j	<u>i</u>			<u>j j.</u>			■ S	Security	Trim
	A3270	Telecom Trim	5	5	0% 25-Aug-25	29-Aug-25									,												■ Te	elecom	Trim
	A3300	Doors & Hardware	5	5	0% 25-Aug-25	29-Aug-25																					II D	Ooors &	Har
	A3280	Set Ceiling Tiles	10	10	0% 08-Sep-25	19-Sep-25						!			! ! !											:		■ Set 0	Geilin
	A3310	Renovation Punchlist	5	5	0% 22-Sep-25	26-Sep-25						:			!								-			:		■ Re	nova
Р	ost Constructi	on	213	213	24-Dec-24	17-Oct-25																							
	A3380	New Building A/B Owner Occupy	5	5	0% 24-Dec-24	31-Dec-24									† !						New	Buildin	g A/B	Owner (	Эссир	y			†
	A3390	New Building A/B Final Occupancy Sign Off	5	5	0% 01-Jan-25	07-Jan-25														į	I Ne≀	v Buildi	ing A/E	Final O	)ccupa	ıncy Si	gn Of	ff	
	A3400	Renovation Build A Owner Occupy	5	5	0% 29-Sep-25	03-Oct-25						1			1											1		į R	enov
	A3410	Rennovation Building A Occupancy Sign Off	5	5	0% 06-Oct-25	10-Oct-25						į	i		i !					i	i					i	į	■ F	Renn
	A3420	Total Project Completetion	5	5	0% 13-Oct-25	17-Oct-25						-			! ! !						- 1								Total

Actual Work 

Remaining Work

Critical Remaining Work

Page 6 of 6	
rage o or o	31

Date	Revision	Checked	Approved
31-Jul-23	Schedule	JD	JD

